

[10/3/2022]
पाराशिष्ट 1

प्रश्न सं. [क. 1467]

WATER RESOURCES DEPARTMENT
GOVERNMENT OF MADHYA PRADESH



UNIFIED SCHEDULE OF RATES
FOR
WORKS OF WATER RESOURCES DEPARTMENT
MADHYA PRADESH

In Force From
01.09.2017

Issued by
Engineer-in-Chief
Water Resources Department Madhya Pradesh
Bhopal

Price Rs. 1000/-

Item No.	Description of Item	Unit	Rate	Remarks
9-12	Earthwork for embankment for breached/ damaged portion of dam/ canal, using selected impervious soil from approved borrow area/ spoil bank in 100 to 150 mm layers (before compaction), including cost of materials, machinery, labour, all other operations such as collection of soil, spreading soil in layer of specified thickness, sorting out, breaking clods, levelling, sectioning edges / sides, watering, compacting to achieve maximum dry density using sheep foot roller/vibratory compactors etc. complete.	cum	80.00	
9-13	Repairing rain cuts/ re-sectioning canal slopes to required lines and grades as directed, using available canal side soil including dressing, packing soil, breaking clods, watering, tamping etc., complete	sqm	4.00	
9-14	Maintenance of canals wherever required, having bed width more than 5m or discharge more than 10 cumecs (as applicable) & depth of canal < 3m by deploying a unit of T-210 or T-110, Dumper/Tractor trolley and 10 numbers of labour, to restore the bed levels and side slopes of canal section, including service road to proper condition, including clearance of all vegetation such as grass, shrubs, bushes etc and disposal of surplus and un-useful earth or borrow of earth, as needed, including cost of all materials, labour and transportation etc. complete.			
9-14.1	For earthen canal	km	33911.00	
9-14.2	For lined canal	km	8478.00	

Item No.	Description of item	Unit	Rate	Remarks
9.15	Maintenance of canals wherever required, having bed width more than 5m or discharge more than 10 cumecs (as applicable) & depth of canal > 3m by deploying a unit of T-210 or T-110, Dumper/Tractor trolley and 10 numbers of labour, to restore the bed levels and side slopes of canal section, including service road to proper condition, including clearance of all vegetation such as grass, shrubs, bushes etc. and disposal of surplus and un use full earth or borrow of earth, as needed, including cost of all materials, labour and transportation etc. complete.			
9.15.1	For earthen canal	km	38756.00	
9.15.2	For lined canal	km	9689.00	
9.16	Maintenance of canals wherever required, having bed width between 1m to 5m or discharge between 1 cumec to 10 cumecs (as applicable) by deploying a unit of JCB, Dumper/ Tractor trolley and 10 numbers of labour to restore the bed levels and side slopes of canal section including service road to proper condition including clearance of all vegetation such as grass, shrubs, bushes etc. and disposal of surplus earth, as needed, including cost of all materials, labour and transportation etc. complete.			
9.16.1	For earthen canal	km	9615.00	
9.16.2	For lined canal	km	2404.00	
	Maintenance of canals wherever required, having bed width less than 1m. or discharge less than 1 cumec (as applicable) by deploying a unit of JCB, Dumper/Tractor trolley and 10 numbers of labour to restore the bed and side slopes of canal section including service road to proper condition including clearance of all vegetation such as grass, shrubs, bushes etc. and disposal of surplus earth or borrow of earth, as needed, including cost of all materials, labour and transportation etc complete.			
9.17.1	For earthen canal	km	2719.00	
9.17.2	For lined canal	km	555.00	