

प्रश्न सं. [क. 2817]

विधान सभा प्रश्न क्र. 2817 (कारांकित)
(तकनीकी स्वीकृति)


OFFICE OF MUNICIPAL CORPORATION MORENA (M.P)


Work : Detailed estimate for construction of under ground storm water Rcc hume pipe drain from Jlwaji ganj culver
wall area road & Gufa mandlr se sadar bazar tak & Chambal colony se radhika palace chauraha tak, Peetambara lodge se
Public rest house tak.


Name of particulars	No.	L	B	H/D	Qty	Rate	units	Amount
Earth work in excavation for foundation, trenches for pipes / cables or drains etc. by mechanical means / manual means (exceeding 30cm in depth.) including ramming of bottom, dressing of sides, disposal of excavated earth including of all lift and lead upto 50m. Disposed earth to be levelled and neatly dressed	1	2920	1.5	1.5	6570	151	cum	992070
Construction of granular sub-base by providing Coarse graded material (CBR>30), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method at OMC and compacting with vibratory roller of 80-100 KN Static weight to achieve the desired density, complete in all respect as per relevant clauses of section-400.	1	2920	1.5	0.15	657	689	cum	452673
Providing & laying levelling course/annular filling in PCC M-15 nominal mix in foundation as per relevant clauses of section 1500, 1700 and 2100.	1	2920	1.5	0.15	657			
	1	2920	0.3	0.4	350.4			
					1007.4	4299	cum	4330812.6
Providing, Laying and Jointing non-pressure (NP4) RCC socket & spigot pipes with rubber gasket joint including testing of joints. 200 mm dia	1	2700			2700	5026	rm	13570200.00
Construction of embankment with approved material having CBR>7 obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting by vibratory rollers to meet requirement of table 300-1, 300-2 and as per relevant clauses of section-300	1	2920	1.5	1.2	5256			
	(-)	1	2920	3.14	0.22	2017.1		
	(-)	1	2920	0.3	0.4	350.4		
					2888.5	108	sqm	311954.11


अनुभाग अधिकारी
मध्य प्रदेश शासन
नगरीय विकास एवं पर्यावरण विभाग

Construction of circular type manhole 900 mm Internal dia. at bottom, 560 mm dia at top, depth of manhole 900 mm, common Burnt Clay Bricks or fly ash bricks of compressive strength not less than 75 Kg/cm ² with 1:4 cement mortar (1 cement : 4 coarse sand), inside & outside plastering minimum 12 mm thick with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement. 20 cm thick foundation in cement concrete 1:3:6 (Nominal Mix) with stone aggregate 40mm nominal size, and making channel in cement concrete 1:2:4 (Nominal Mix) with stone aggregate 20mm nominal size including finishing the channel to shape, including providing and fixing footrest, manhole cover and frame etc. complete. (only excavation as per actual shall be paid separately) fixing of heavy duty (HD-20) SFRC cover and frame as per IS 12592 fixed in Cement concrete 1:2:4 (nominal mix) with stone aggregate 20mm nominal size including centering and shuttering etc. complete as per standard drawing. Depth of manhole shall be considered as the vertical distance from top of the manhole cover to the outgoing invert of main drain channel. (as per Drawing No. - 13-A)	200				200	7950	each	1590000.00
(Extra depth shall be paid extra) ✓								
Providing and laying Cement Concrete grade M-20 (Nominal mix 1:1.5:3) with 20 mm graded crushed stone aggregate, mixing shall be in mechanical mixer, laying with paver compacting by use of pin, plate / screed vibrators including form work by strong steel girders fixed by spikes, separation membrane 125 micron thick, i/c cutting of joints @ 4 to 5 m interval & filling it with hot applied bituminous sealant (with out dowel bars). (max. thickness 20cm)	1	2920	1.7	0.15	744.6	5029	cum	3744593.40
Total								24992303.11
Add 12% GST								2999076.37
total								27991379.49
Grand total								27992000


Sub Engineer
Municipal corporation Morena


Assistant Engineer
Municipal corporation Morena


Executive Engineer
Municipal corporation Morena


Superintendent Engineer
Municipal Corporation MORENA

अनुभाग अधिकारी
मध्य प्रदेश शासन
जननी विकास एवं पर्यावरण विभाग

विधान सभा प्रश्न क्र. 2817 (कार्यक्र. 6)
(प्रशासनिक स्वीकृति)
कार्यालय नगरपालिक निगम मुरैना (म0प्र0)

प्रशासक संकल्प क्र. 11

दिनांक 3/11/2021

विषय:-माननीय श्री नरेन्द्र सिंह तोमर सांसद मुरैना/केंद्रीय कृषि मंत्री भारत सरकार के द्वारा प्रस्तावित निर्माण कार्य हेतु शासन से विशेष निधि प्राप्त करने बाबत।

---000---

प्रकरण प्रस्तुत हुआ, कार्यवाही का अवलोकन किया गया। विभागाध्यक्ष समिति की अनुशंसा अनुसार निम्नलिखित निर्माण कार्य के लिये शासन से विशेष निधि प्राप्त करने हेतु प्रशासनिक स्वीकृति प्रदान की जाती है।

1. एम.एस.रोड के दोनो तरफ नाला निर्माण - लागत राशि रु.249.00लाख
2. एम.एस.रोड के दोनो तरफ पेवर ब्लाक फुटपाथ निर्माण - लागत राशि रु.105.00 लाख
3. जौरा रोड से ए.बी.रोड तक पेवर ब्लाक निर्माण - लागत राशि रु.200.00 लाख

उक्तानुसार कुल रूपये रु.554.00 लाख के प्रस्ताव संचालनालय नगरीय प्रशासन एवं विकास म.प्र. भोपाल को प्रेषित किये जावें।

आशीष सरस्वती

प्रशासक

नगर पालिक निगम मुरैना

अनुभाग अधिकारी
मध्यप्रदेश शासन
नगरीय विकास एवं पर्यावरण विभाग