


Survey Report Of Jamuniya Gonda Khoh Minor Tank

1	Name of proposed schemes	Jamuniya Gondakhoh Tank Project(Without Canal)
2	Block	Begamganj
3	District	Raisen
4	Toposheet No.	55-1/6 & 55-1/7
5	Latitude	23° 30'25.54" N
6	Longitude	78° 21'2.23" E
7	Catchment area	9.12 sq.km.
8	Assembly Consitituency	153 Silwani
9	Proposer (who suggested the scherme)	sh. Rampal singh M.L.A.
10	Proosed Rabi Irrigation area	530.00 hac.
11	Benificery cultivators	385
12	Estimated total cost	6166.249 lakh
13	Land acquistition area	104.40 hac.
14	Contruction cost	557.36 lakh
15	Submergence area total	104.40 ha.
16	Government land	8.00 ha.
17	Forest land	86.80 ha.
18	Private land (irrigated)	9.60 ha.
19	Is the percentage of submergence of the land of the area proposed for irrigation is less then 10%	No. Percentage of submergence is 19.70% which is more than 10%
20	Forest submergence if any submergence of forest land	80% to 90% forest land is coming under submergence
21	Is the cost per Hac.likely to reasonble	No. cost is coming out to be 6.17 Lakh/ Hac.
22	Remarks and recommendation	<p>The submergece of land exceeds 10% and does not fullfill the department criteria.</p> <p>The cost per hac. Of the projcet is high and not in accordance with the prescribde criteria, hence the scheme may not be vaible.</p> <p>As per study of toposheet about 80% to 90% of the forest land will come under submergence .</p> <p>Hence the above scheme is proposed for deletion.</p>


Sub Engineer

Semri Project Sub
Division Begamganj


Sub Divisional officer

Semri Project Sub Division
Begamganj


Executive Engineer

water resources division
Raisen